

BILANS ROBÓT ZIEMNYCH – Linia trasowania 35

Pikieta	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Catk. obj. wykopu	Catk. obj. nasypu	Obj. netto
7+180.10	2.28	0.00	0.00	0.00	0.00	0.00	0.00
7+197.16	1.84	0.01	35.14	0.11	35.14	0.11	35.03
7+213.00	1.75	0.02	28.39	0.23	63.52	0.34	63.19
7+230.83	2.05	0.00	33.88	0.16	97.41	0.50	96.91
7+258.09	2.36	0.05	60.10	0.70	157.51	1.19	156.32
7+278.53	1.53	0.13	39.72	1.86	197.23	3.05	194.18
7+293.46	1.96	0.06	26.03	1.37	223.26	4.42	218.84
7+313.60	2.38	0.02	43.72	0.83	266.99	5.25	261.74
7+338.46	1.89	0.02	53.10	0.52	320.08	5.77	314.31
7+357.59	1.43	0.10	31.72	1.07	351.81	6.85	344.96
7+373.16	1.72	0.11	24.60	1.40	376.41	8.24	368.16
7+389.37	2.23	0.34	32.02	3.46	408.43	11.70	396.73
7+400.43	2.12	0.08	24.05	2.27	432.48	13.97	418.51
7+423.28	1.98	0.25	46.82	3.78	479.30	17.74	461.55
7+454.41	2.00	0.09	61.97	5.28	541.27	23.02	518.25
7+470.21	2.63	0.03	36.61	0.96	577.88	23.98	553.89
7+472.25	3.44	0.00	6.19	0.03	584.07	24.02	560.05
7+496.37	2.39	0.08	70.32	1.08	654.39	25.09	629.30
7+498.63	1.79	0.02	4.74	0.12	659.13	25.22	633.91
7+518.24	2.30	0.00	40.07	0.23	699.19	25.44	673.75
7+534.67	2.49	0.00	39.24	0.01	738.44	25.46	712.98
7+551.69	2.04	0.00	38.49	0.01	776.93	25.46	751.47
7+577.60	1.84	0.12	50.25	1.56	827.18	27.02	800.16
7+617.88	2.92	0.03	95.85	2.96	923.04	29.98	893.05
7+661.97	1.38	0.12	94.64	3.33	1017.67	33.32	984.36
7+710.53	1.05	0.32	59.13	10.65	1076.81	43.97	1032.84
7+749.82	1.07	0.12	41.69	8.46	1118.49	52.43	1066.07
7+785.91	2.29	0.00	60.64	2.48	1179.13	54.91	1124.62
7+816.25	2.55	0.00	73.37	0.00	1252.90	54.91	1197.99
7+839.73	2.00	0.00	53.02	0.01	1306.01	54.91	1251.01

+30 m3 pozyskane z regulacji/odmulenia rowów w celu zasypania dołów po karpinach